



*Is pleased to present you with  
the following quote*

**CITY OF WILLOUGHBY HILLS  
ATTN: MARK GRUBISS**  
  
**HENDERSON MUNIBODY FULL SNOW  
AND ICE CONTROL SINGLE AXLE  
PACKAGE**  
  
**8/10/2015**

*HENDERSON TRUCK EQUIPMENT IS A DIVISION OF HENDERSON MANUFACTURING AND THUS  
ALLOWS US THE ABILITY TO FOCUS ON A SPECIFIC PRODUCT LINE, HENDERSON. OUR OHIO  
FACILITY ONLY INSTALLS HENDERSON PRODUCTS AND THEREFORE WE ARE ABLE TO OFFER A  
SUPERIOR INSTALLATION AND SERVICE TO OUR CUSTOMERS.*

**\*\*\*2 YEAR FULL WARRANTY ON ALL EQUIPMENT\*\*\***

*\*2 YEAR FULL WARRANTY ON ALL EQUIPMENT ONLY AVAILABLE WHEN A HENDERSON FACTORY  
OWNED UPFIT FACILITY DOES THE INITIAL INSTALLATION AND UP-FIT ON THE ENTIRE BUILD AND  
SERVICE AND WARRANTY WORK THERE AFTER.*

*\*ALL MOUNTING 100% TO CITY OF WILLOUGHBY HILLS SPECIFICATIONS*

*\*PREDELIVERY INSPECTION AT OUR FACILITY PRIOR TO PAINT*

*\*WARRANTY WORK AND SERVICE WORK- HENDERSON TRUCK EQUIPMENT WILL PICK UP  
THE VEHICLE AT YOUR LOCATION AND MAKE NECESSARY REPAIRS AND RETURN TO  
YOUR FACILITY.*

*\*ALL EQUIPMENT AND YOUR CHASSIS ARE FULLY INSURED WHILE IN HENDERSON TRUCK  
EQUIPMENTS POSSESSION.*

**TOTAL INSTALLED PRICE \$77,114.00**

**ESTIMATED LEAD TIME 90 TO 120 DAYS AFTER RECEIVING CHASSIS AND  
ALL RELATED SNOW AND ICE CONTROL PACKAGE EQUIPMENT**

**HENDERSON TRUCK EQUIPMENT-OHIO  
DAN PERRY-OHIO SALES REP.**

SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_  
440-226-4690 CELL  
[DPERRY@HENDERSONPRODUCTS.COM](mailto:DPERRY@HENDERSONPRODUCTS.COM)

CONTRACT ACCEPTANCE: \_\_\_\_\_ DATE: \_\_\_\_\_

TITLE: \_\_\_\_\_ PURCHASE ORDER #: \_\_\_\_\_

**SEE ATTACHED SPECIFICATIONS:**

**HENDERSON SNOW PLOW HITCH**

HENDERSON MODEL HFF-LP -QCC FRONT FRAME SNOW PLOW HITCH  
HENDERSON QUICK HITCH WITH PIN AND LOOP  
HENDERSON FULL 5/8" STEEL PUSH PLATES  
OEM BUMPERS  
4" X 10" LIFTING CYLINDER  
5 POSITION TELESCOPIC LIFT ARM  
FOLDS FLAT WHEN NOT IN USE  
SANDBLASTED AND PRIMED  
PAINTED AND INSTALLED

**HENDERSON RSP SNOW PLOW**

HENDERSON RSP 10' X 42" REVERSIBLE SNOW PLOW  
FULL TRIP 10GA STEEL MOLDBOARD WITH INTEGRAL SHIELD  
FULL TRIP HEAVY DUTY 5 POSITION ADJUSTABLE COMPRESSION SPRINGS  
4" X 4" X 3/4" HD BASE ANGLE  
5/8" X 8" STANDARD CUTTING EDGE  
HEAVY DUTY FULL WIDTH 7 POINT STRUCTURAL TUBEULAR PUSH BEAM  
4" X 10" ANGLE CYLINDERS TO MATCH HITCH LIFT CYLINDER  
100% CONTINUOUS WELDED  
HENDERSON BUILT IN LEVEL LIFT SYSTEM  
PIN & LOOP HITCH CONNECTION SYSTEM  
12" HENDERSON RUBBER SNOW DEFLECTOR  
36" ORANGE PLOW SIDE MARKERS  
1/2" STAINLESS STEEL QUICK COUPLER  
PARKING JACK  
INSTALLED

**HENDERSON COMBINATION DUMP BODY**

HENDERSON MUNI-BODY II 10' STAINLESS STEEL DUMP BODY  
CROSSMEMBERLESS-UNIBODY DESIGN  
22 DEGREE SLOPED SIDES  
CHAIN CONVEYOR WITH FRONT AND REAR CENTER DISCHARGE  
STAINLESS STEEL CONSTRUCTION  
ENTIRE BODY IS CONTINUOUSLY WELDED  
SLOPED LOWER DIRT SHEDDING RUB RAIL.  
10' LONG  
7' WIDTH  
36" SIDES  
48" MANUAL TAILGATE WITH GREESABLE HINGES  
HORIZONTAL BRACES ON TAILGATE  
1/4" AR400 STEEL FLOOR 200,000 PSI IMPACT RESISTANCE  
SLOPED BOX TOP RAIL 4"x5" SEAMLESS AND BOXED  
HORIZONTAL 7 GAUGE STAINLESS STEEL SIDE BRACE  
FULL DEPTH REAR CORNER POST 7 GAUGE STAINLESS STEEL  
22"X86" STAINLESS STEEL CAB SHIELD  
REAR MOUNTED MOTOR AND GEARCASE FOR CONVEYOR  
3/16" AR 400 STEEL CONVEYOR COVER  
DOUBLE CONVEYOR CROSS BARS

20" HENDERSON POLY FRONT SPINNER ASSEMBLY  
HENDERSON DIRECT CAST REAR SPINNER ASSEMBLY  
HENDERSON STAINLESS STEEL FOLD UP LADDER  
HEAVY DUTY TOP GRATE STAINLESS STEEL SCREENS  
ALL LED FMVSS # 108 MARKER LIGHTS  
INSTALLED

### HENDERSON HOIST

HENDERSON MODEL CS FRONT TELESCOPIC MAILHOT HOIST  
29 TON CAPACITY  
FULL DOUBLE ACTING (POWER UP AND ALL THE WAY DOWN)  
4" INSIDE DIAMETER CYLINDER BASE TUBE  
ALL CYLINDER STAGES FULLY NITRIDED FOR CORROSION AND WEAR RESISTANCE  
HOIST IS PHOSPHATE RINSED, EPOXY PRIMED, AND FINISH PAINTED BLACK  
HOIST MOUNTED IN FRONT OF BODY-FLAT HEADSHEET  
9" MOUNTING HEIGHT  
6"x8"x1/2" STRUCTURAL ANGLE WITH 2" STAINLESS STEEL PINS  
GREASEABLE REAR PINS  
INSTALLED

### ELECTRICAL SYSTEM

WHELEN LED SYSTEM  
LED AMBER/GREEN/WHITE STROBES MOUNTED IN SELF LEVELING STAINLESS STEEL  
BOXES MOUNTED TO THE SIDE OF THE CAB SHIELD  
LED AMBER/GREEN/WHITE LIGHTS CUT INTO REAR POST  
LED BACK UP LIGHTS CUT INTO REAR POST  
LED STOP/TAIL/TURN CUT INTO REAR POST  
LED SPINNER HEAVY DUTY WHELEN LIGHT  
MODEL SK-10 BODY UP LIGHT  
WHELEN BACK UP ALARM  
ALL ONE PIECE WIRING FROM POWER SOURCE TO ELECTRICAL ITEM  
ALL WIRING WILL BE PROPERLY RUN TO AVOID SHARP EDGES AND PINCH POINTS  
ALL WIRING WILL BE PROPERLY FUSED WITH NO BUTT JOINTS OR SPLICES  
FACTORY REAR CHASSIS LIGHTS TO BE REINSTALLED  
HENDERSON PDP POWER DISTRIBUTION PANEL  
ALL LED FMVSS # 108 MARKER LIGHTS  
SNOW PLOW LIGHTS WITH HENDERSON STAINLESS STEEL MOUNTING BRACKETS  
ALL ONE PIECE WIRING WITH COPY OF WIRING SCHEMATIC  
INSTALLED 100% TO YOUR SPECIFICATIONS

### CENTRAL HYDRAULIC SYSTEM

CERTIFIED POWER-STORMGUARD/LOAD SENSING SYSTEM  
DANFOSS FRONT MOUNTED PUMP  
CONTROL VALVE TO RUN BODY CONVEYOR, HOIST, SNOW PLOW, FRONT & REAR  
SPINNER AND WILL ALSO HAVE A VALVE IN PLACE FOR FUTURE PRE-WET APPLICATION  
ELECTRIC OVER HYDRAULIC CONTROLS  
CERTIFIED POWER XDS ELECTRIC CONTROLS WITH ARM REST  
HENDERSON STEEL FLOOR PLATE

HENDERSON BEHIND CAB 40-GALLON STAINLESS STEEL OIL RESERVOIR AND VALVE ENCLOSURE  
ALL WEATHERHEAD "RHINO-GUARD" HOSES AND FITTINGS  
ALL STAINLESS STEEL QUICK COUPLERS  
ALL PRESSURE HOSES SAE 100R2  
ALL FITTING JIC STYLE  
MID-STATE STAINLESS STEEL HYDRAULIC REAR TUBES MOUNTED WITH POLY BUSHINGS  
MID-STATE STAINLESS STEEL FRONT TUBES MOUNTED WITH POLY BUSHINGS  
HYDRUALIC SYSTEM TO BE FULLY INSTALLED, TESTED AND CALIBRATED

**MISCELLANEOUS**

3/4" PINTLE PLATE WITH 7 PIN PLUG, D-RINGS, AND 8 ADJUSTABLE HITCH MOUNTING HOLES  
WOOD SIDE BOARDS PAINTED COLOR OF YOUR CHOICE  
STAINLESS STEEL SHOVEL HOLDER  
HENDERSON QUICK RELEASE FULL REAR MUD FLAPS  
RED & WHITE REFLECTIVE TAPE BOTH SIDES AND TAILGATE  
CHASSIS AND UNDERSIDE OF BODY WILL BE UNDERCOATED

**NONCOMPLIANCE TO THE LIQUIDATED DAMAGES CLAUSE:**

**HENDERSON TRUCK EQUIPMENT WILL NOT COMPLY TO THE DELIVERY GUIDELINE SET BY THE CITY OF WILLOUGHBY HILLS OF 120 DAYS AFTER CONTRACT AWARD DATE AND \$200.00 PER CALLENDAR DAY PENALTY EVERYDAY THEREAFTER UNTIL THE COMPLETED UNIT IS DELIVERED.**

**HENDERSON TRUCK EQUIPMENTS ESTIMATED DELIVERY OF THE COMPLETED UNIT TO THE CITY OF WILLOUGHBY HILLS IS 90 TO 120 DAYS AFTER THE CHASSIS AND ALL RELATED SNOW AND ICE CONTROL EQUIPMENT (TRUCK BODY, PLOW, SPREADER, HYDRAULIC SYSTEM, ELECTRICAL ETC.) HAS ARRIVED AT OUR FACILITY TO BE INSTALLED.**